
RESTROOM & ADA DETAILS (CONT.)



STALL SIZE: 36" (ADA 2010 Section 608.2.1) 21

SEAT HEIGHT: 17" MIN TO 19" MAX AFF TO TOP OF SEAT (ADA 2010 610.3)


GRAB BAR HEIGHT: 33" MIN TO 36" MAX AFF TO TOP OF GRIPPING SURFACE (ADA 2010 609.4) 23

THRESHOLD: 0.5" MAX (ADA 2010 Section 608.7) 24

CONTROLS: 38" MIN TO 48" MAX AFF, SIDE WALL OPPOSITE SEAT (ADA 2010 608.5.1) 54

- FOLDING SEAT ON WALL OPPOSITE CONTROLS
- PROVIDE BLOCKING FOR SEAT + GRAB BARS
- HAND SHOWER WITH 59" HOSE MIN PER 608.6

1 / A9.2 ACCESSIBLE TRANSFER SHOWER



TURNING DIAMETER: 60" (ADA 2010 Section 304.3.1) 21

ROUTE WIDTH: 36" MIN CLEAR (ADA 2010 Section 403.5.1) 26


CLEAR FLOOR SPACE: 30" x 48" MIN AT FIXTURES

T-TURN ALT: 60" x 60" T-SHAPED PERMITTED

FLOOR SLOPE: 1:48 (2%) MAX ANY DIRECTION

- TURNING SPACE MAY OVERLAP KNEE/TOE CLEARANCE
- DOOR SWING SHALL NOT REDUCE REQUIRED SPACE
- MAINTAIN CLEAR FLOOR PER 304 AND 305

2 / A9.2 ACCESSIBLE TURNING SPACE



SEAT HEIGHT: 17" MIN TO 19" MAX AFF TO TOP OF SEAT (ADA 2010 604.4) 27

C/L TO SIDE WALL: 18" (ADA 2010 Section 604.2) 23

FLUSH CONTROL HT: 44" MAX AFF (ADA 2010 Section 604.6) 26

TP DISPENSER OUTLET: 15" MIN TO 48" MAX AFF (ADA 2010 604.7)


CLEAR FLOOR W: 60" MIN (ADA 2010 Section 604.3.1)

CLEAR FLOOR D: 56" MIN (WALL-HUNG) (ADA 2010 Section 604.3.1)

- FLUSH CONTROL ON OPEN (WIDE) SIDE OF FIXTURE
- PROVIDE SIDE + REAR GRAB BARS PER 604.5

3 / A9.2 ACCESSIBLE WATER CLOSET

1/2" = 1'-0"



MEMBRANE: FLUID-APPLIED WATERPROOFING MEMBRANE 18

FLOOR SLOPE: 1/4" PER FT TO FLOOR DRAIN 34

COVE BASE: INTEGRAL COVE BASE, 6" UP WALL 55

MEMBRANE TURN-UP: TURN MEMBRANE UP 6" MIN AT WALLS

FLOOD TEST: 24-HR FLOOD TEST PRIOR TO TILE

- MEMBRANE CONTINUOUS UNDER FLOOR DRAIN FLANGE
- LAP MEMBRANE TO DRAIN CLAMPING RING
- SLOPE SUBSTRATE, DO NOT SLOPE FILL ALONE

4 / A9.2 RESTROOM FLOOR WATERPROOFING

3" = 1'-0"

KEYNOTES

21	01 10 00 ACCESSIBLE MOUNTING HEIGHT - SEE ADA REQUIREMENTS	**23**	10 28 00 GRAB BAR - MOUNT PER ADA REQUIREMENTS
24	01 10 00 ACCESSIBLE ROUTE - MAINTAIN 36" MIN. CLEAR WIDTH	**54**	22 11 00 PLUMBING CHASE - SEE PLUMBING DRAWINGS
26	06 41 00 KNEE AND TOE CLEARANCE PER ADA	**48**	09 30 00 TILE FINISH - SEE FINISH SCHEDULE
55	22 13 00 FLOOR DRAIN - SEE PLUMBING PLAN		

SHEET NOTES

1. GENERAL REQUIREMENTS: SPECIFIED IN SECTION 01 10 00.

KEYNOTES

1. ACCESSIBLE MOUNTING HEIGHT - SEE ADA REQUIREMENTS: SECTION 01 10 00
2. GRAB BAR - MOUNT PER ADA REQUIREMENTS: SECTION 10 28 00
3. ACCESSIBLE ROUTE - MAINTAIN 36" MIN. CLEAR WIDTH: SECTION 01 10 00
4. KNEE AND TOE CLEARANCE PER ADA: SECTION 06 41 00
5. TILE FINISH - SEE FINISH SCHEDULE: SECTION 09 30 00
6. PLUMBING CHASE - SEE PLUMBING DRAWINGS: SECTION 22 11 00
7. FLOOR DRAIN - SEE PLUMBING PLAN: SECTION 22 13 00

NOT PROVIDED — BY OTHERS
APPLICANT / OWNER

CONSULTANTS

STRUCTURAL	NOT PROVIDED — BY OTHERS
CIVIL	NOT PROVIDED — BY OTHERS
MECHANICAL	NOT PROVIDED — BY OTHERS
PLUMBING	NOT PROVIDED — BY OTHERS
ELECTRICAL	NOT PROVIDED — BY OTHERS
LANDSCAPE	NOT PROVIDED — BY OTHERS
FIRE PROTECTION	NOT PROVIDED — BY OTHERS
GEOTECHNICAL	NOT PROVIDED — BY OTHERS

REVIEW

Prepared for review by the design professional of record. Not for construction or permit submission.

PROJECT

Architecture.Engineering — L courtyard study

FICTIONAL STUDY: NO REAL PARCEL
ARCHITECTUREENGINEERING — L COURTYARD STUDY
OCCUPANCY R-2, M · CONSTRUCTION NOT PROVIDED — BY OTHERS · STORIES 4

REVISIONS

MARK	DATE	DESCRIPTION

REGISTER

Project	AE-STUDY-L01
Issue	NOT PROVIDED — BY OTHERS
Date	NOT PROVIDED — BY OTHERS
Drawn	NOT PROVIDED — BY OTHERS
Scale	AS NOTED
Phase	CONSTRUCTION DOCUMENTS

OPEN ISSUE

The set's open issue is stated on the cover, G0.01.

RESTROOM & ADA DETAILS (CONT.)

SHEET

A9.2