
INTERIOR MISCELLANEOUS DETAILS (CONT.)




WALL HEIGHT: 36"-42" AFF TO TOP OF CAP (3)
FRAMING: 2x4 OR 2x6 STUDS @ 16" O.C. (47)
CAP: SOLID WOOD OR PLAM CAP, EASED EDGE
BLOCKING: CONTINUOUS BLOCKING AT CAP + BASE
BASE ANCHORAGE: ANCHOR SOLE PLATE TO FLOOR @ 24" O.C.

- PROVIDE BLOCKING FOR ANY MOUNTED ITEMS
- GWB BOTH FACES, WRAP CAP CORNERS
- VERIFY GUARD HEIGHT WHERE FALL HAZARD EXISTS

1 / A9.6 **LOW KNEE WALL**

1" = 1'-0"




UNIT TYPE: SMART PARCEL LOCKER BANK (3)
OPERABLE PART: TOUCHSCREEN/KIOSK 15"-48" AFF (10)
CLEAR FLOOR SPACE: 30" x 48" AT KIOSK + ACCESSIBLE BAYS
POWER: DEDICATED 120V CIRCUIT + DATA
FRONT CLEARANCE: 36" MIN CLEAR IN FRONT OF BANK
ANCHORAGE: ANCHOR TO FLOOR + WALL PER MFR

- PROVIDE BLOCKING AND BACKING AT WALL ANCHORS
- COORDINATE POWER + DATA WITH ELECTRICAL
- PROVIDE ACCESSIBLE BAYS WITHIN REACH RANGE 308

3 / A9.6 **PACKAGE LOCKER BANK**

1/2" = 1'-0"




UNIT TYPE: USPS-APPROVED CBU (4C COMPLIANT) (3)
TENANT BOX LOW: 28" MIN AFF TO LOWEST BOX (10)
TENANT BOX HIGH: 67" MAX AFF TO HIGHEST BOX
PARCEL COMPARTMENT: PROVIDE INTEGRAL PARCEL LOCKERS
CLEAR FLOOR SPACE: 30" x 48" AT EACH UNIT
OUTGOING MAIL: COLLECTION SLOT 36"-48" AFF

- ANCHOR TO PAD OR FLOOR PER MFR REQUIREMENTS
- PROVIDE BLOCKING FOR WALL-MOUNT UNITS
- USPS APPROVAL REQUIRED PRIOR TO INSTALL

2 / A9.6 **MAILBOX CLUSTER UNIT**

1/2" = 1'-0"



COUNTER HEIGHT: 36"-42" AFF TO TOP OF COUNTER (3)
SUPPORT BRACKETS: STEEL BRACKETS @ 32" O.C. MAX (50)
BACKSPLASH: 4" BACKSPLASH, SEALED TO WALL
COUNTERTOP: SOLID SURFACE OR PLAM, EASED EDGE
BLOCKING: CONTINUOUS BLOCKING AT BRACKET LINE

- PROVIDE CONTINUOUS BLOCKING FOR BRACKETS
- SEAL BACKSPLASH JOINT WITH SILICONE
- VERIFY BRACKET CAPACITY FOR COUNTER LOAD

4 / A9.6 **STANDING-HEIGHT COUNTER**

1" = 1'-0"

KEYNOTES

3	06 10 00 PROVIDE BLOCKING AS REQUIRED FOR MOUNTING	**47**	09 21 00 GWB FINISH - SEE FINISH SCHEDULE
10	01 10 00 MAINTAIN CLEARANCES PER MANUFACTURER REQUIREMENTS	**50**	12 36 00 COUNTERTOP - SEE SPECIFICATIONS

SHEET NOTES

1. GENERAL REQUIREMENTS: SPECIFIED IN SECTION 01 10 00.

KEYNOTES

1. PROVIDE BLOCKING AS REQUIRED FOR MOUNTING: SECTION 06 10 00
2. MAINTAIN CLEARANCES PER MANUFACTURER REQUIREMENTS: SECTION 01 10 00
3. GWB FINISH - SEE FINISH SCHEDULE: SECTION 09 21 00
4. COUNTERTOP - SEE SPECIFICATIONS: SECTION 12 36 00

NOT PROVIDED — BY OTHERS
APPLICANT / OWNER

CONSULTANTS

STRUCTURAL	NOT PROVIDED — BY OTHERS
CIVIL	NOT PROVIDED — BY OTHERS
MECHANICAL	NOT PROVIDED — BY OTHERS
PLUMBING	NOT PROVIDED — BY OTHERS
ELECTRICAL	NOT PROVIDED — BY OTHERS
LANDSCAPE	NOT PROVIDED — BY OTHERS
FIRE PROTECTION	NOT PROVIDED — BY OTHERS
GEOTECHNICAL	NOT PROVIDED — BY OTHERS

REVIEW

Prepared for review by the design professional of record. Not for construction or permit submission.

PROJECT

Architecture.Engineering — L courtyard study

FICTIONAL STUDY: NO REAL PARCEL
ARCHITECTURE.ENGINEERING — L COURTYARD STUDY
OCCUPANCY R-2, M · CONSTRUCTION NOT PROVIDED — BY OTHERS · STORIES 4

REVISIONS

MARK	DATE	DESCRIPTION

REGISTER

Project	AE-STUDY-L01
Issue	NOT PROVIDED — BY OTHERS
Date	NOT PROVIDED — BY OTHERS
Drawn	NOT PROVIDED — BY OTHERS
Scale	AS NOTED
Phase	CONSTRUCTION DOCUMENTS

OPEN ISSUE

The set's open issue is stated on the cover, G0.01.

INTERIOR MISCELLANEOUS DETAILS (CONT.)

SHEET

A9.6