ABBREVIATIONS

AB	ANCHOR BOLT
ACT	ACOUSTICAL TILE
AD	AREA DRAIN
ADJ	ADJACENT
AFF	ABOVE FINISH FLOOR
AGG	AGGREGATE
AHJ	AUTHORITY HAVING JURISDICTION
ALT	ALTERNATE
ALUM	ALUMINUM
APPROX	APPROXIMATE
ARCH	ARCHITECT(URAL)
BB	BOND BEAM
BD	BOARD
BLDG	BUILDING
BLK	BLOCK
BLKG	BLOCKING
BM	BEAM
BOT	BOTTOM
BRG	BEARING
BRK	BRICK
BUR	BUILT-UP ROOF
CAB	CABINET
CB	CATCH BASIN
C/C	CENTER-TO-CENTER
CG	CORNER GUARD
CI	CAST IRON
CJ	CONTROL JOINT
CL	CENTER LINE
CLG	CEILING
CLR	CLEAR(ANCE)
CMU	CONCRETE MASONRY UNIT
CO	CLEAN OUT
COL	COLUMN
CONC	CONCRETE
CONST	CONSTRUCTION
CONT	CONTINUOUS
CORR	CORRIDOR
CP	CONCRETE PIPE
CTR	CENTER
DBL	DOUBLE
DEMO	DEMOLITION
DIA	DIAMETER
DIM	DIMENSION
DN	DOWN
DR	DOOR
DS	DOWN SPOUT
DTL	DETAIL
DWG	DRAWING
EA	EACH
EIFS	EXT. INSULATION FINISH SYS.
ELEC	ELECTRICAL
ELEV	ELEVATION
ENCL	ENCLOSURE
ENG	ENGINEER
EOS	EDGE OF SLAB
EQ	EQUAL
EQUIP	EQUIPMENT
ETR	EXISTING TO REMAIN
EW	EACH WAY
EWC	ELECTRIC WATER COOLER
EXH	EXHAUST
EXTG	EXISTING
EXP.JT	EXPANSION JOINT
FA	FIRE ALARM
FD	FLOOR DRAIN
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER CABINET
FF	FINISH FLOOR
FHC	FIRE HOSE CABINET
FIN	FINISH(ED)
FLR	FLOOR
FLUOR	FLUORESCENT
FND	FOUNDATION
FO	FACE OF
FOC	FACE OF CONCRETE
FOF	FACE OF FINISH
FOM	FACE OF MASONRY
FOS	FACE OF STUD
FRET	FIRE RETARDANT (TREATED)
FRAT	FIRE RATED
FSD	FIRE SEPARATION DISTANCE
FT	FOOT
FTG	FOOTING
FX	FIRE EXTINGUISHER
GA	GAGE, GAUGE
GALV	GALVANIZED
GB	GRAB BAR
GC	GENERAL CONTRACTOR
GCB	GYPSUM CEILING BOARD
GP	GYPSUM PLASTER
GWB	GYPSUM WALL BOARD
GYP	GYPSUM
HB	HOSE BIB
HC	HOLLOW CORE
HD	HEAVY DUTY
HDWR	HARDWARE
HDWD	HARDWOOD
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HP	HIGH POINT
HR	HOUR
HT	HEIGHT
HVAC	HEATING/VENTING/AIR COND.
HW	HOT WATER
IBC	INTL. BUILDING CODE
ID	INSIDE DIAMETER
IN	INCH
INSUL	INSULATION
INT	INTERIOR
INV	INVERT ELEVATION
JAN	JANITOR
JST	JOIST
JT	JOINT
KD	KNOCK DOWN
KIT	KITCHEN
KO	KNOCK OUT
KP	KICK PLATE
LAB	LABORATORY
LAM	LAMINATE
LAV	LAVATORY
LF	LINEAL FEET
LH	LEFT HAND
LP	LOW POINT
LVR	LOUVER
MAS	MASONRY
MATL	MATERIAL
MAX	MAXIMUM
MB	MACHINE BOLT
MDF	MAIN DISTRIBUTION FRAME
MECH	MECHANICAL
MFR	MANUFACTURER
MH	MANHOLE
MIN	MINIMUM
MISC	MISCELLANEOUS
MO	MASONRY OPENING
MOD	MODULAR
MR	MOISTURE RESISTANT
MTL	METAL
NIC	NOT IN CONTRACT
NRC	NOISE REDUCTION COEFF.
NTS	NOT TO SCALE
OA	OVERALL
OC	ON CENTER(S)
OD	OUTSIDE DIAMETER
OFCI	OWNER FURN., CONTR. INST.
OH	OVERHEAD
OPG	OPENING
OPP	OPPOSITE
ORD	OVERFLOW ROOF DRAIN
PB	PARTICLE BOARD
PC	PRECAST CONCRETE
PERF	PERFORATED
PERIM	PERIMETER
PL	PROPERTY LINE
PLAM	PLASTIC LAMINATE
PLF	POUNDS/LINEAL FOOT
PR	PAIR
PSF	POUNDS/SQUARE FOOT
PSI	POUNDS/SQUARE INCH
PTD	PAPER TOWEL DISPENSER
PVC	POLYVINYL CHLORIDE
PWD	PLYWOOD
QT	QUARRY TILE
QTY	QUANTITY
R	RISERS
RA	RETURN AIR
RAD	RADIUS
RC	RESILIENT CHANNEL
RD	ROOF DRAIN
REF	REFERENCE
REFRIG	REFRIGERATOR
REINF	REINFORCE(D)
REQ'D	REQUIRED
RES	RESILIENT
REV	REVISION(S)
RH	RIGHT HAND
RM	ROOM
RO	ROUGH OPENING
ROW	RIGHT-OF-WAY
SBC	STANDARD BUILDING CODE
SC	SOLID CORE
SCH	SCHEDULE
SD	STORM DRAIN
SEC	SECTION
SF	SQUARE FEET
SHT	SHEET
SHWR	SHOWER
SIM	SIMILAR
SMS	SHEET METAL SCREW
SND	SANITARY NAPKIN DISPOSAL
SPEC	SPECIFICATION
SQ	SQUARE
SS	STAINLESS STEEL
STL	STEEL
STD	STANDARD
STN	STAIN
STRUC	STRUCTURAL
SUSP	SUSPENDED
SV	SHEET VINYL
SW	SWITCH
SYM	SYMMETRIC(AL)
T	TREADS
T&G	TONGUE & GROOVE
TB	TACKBOARD
TC	TOP OF CURB
TEL	TELEPHONE
TEMP	TEMPORARY
THK	THICK(NESS)
THRES	THRESHOLD
TMP	TOP OF MASONRY PARAPET
TOB	TOP OF BEAM
TOC	TOP OF CONCRETE
TOP	TOP OF PARAPET
TOS	TOP OF STEEL
TOW	TOP OF WALL
TPD	TOILET PAPER DISPENSER
TV	TELEVISION
TYP	TYPICAL
UNF	UNFINISHED
UNO	UNLESS OTHERWISE NOTED
VB	VAPOR BARRIER
VCT	VINYL COMPOSITE TILE
VENT	VENTILATION
VERT	VERTICAL
VIF	VERIFY IN FIELD
VNR	VENEER
VT	VINYL TILE
VWC	VINYL WALL COVERING
W	WIDE
W/	WITH
WC	WATER CLOSET
WD	WOOD
WDW	WINDOW
WG	WIRE GLASS
WH	WALL HUNG
WM	WIRE MESH
W/O	WITHOUT
WP	WATERPROOFING
WR	WATER REPELLENT
WSCT	WAINSCOT
WT	WEIGHT
W/W	WALL-TO-WALL
WWF	WELDED WIRE FABRIC
YD	YARD

ARCHITECTURAL SYMBOLS

- SECTION / BUILDING SECTION MARKER
- DETAIL CALLOUT
- ELEVATION MARKER
- GRID LINE MARKER
- MATCHLINE MARKER
- REVISION CLOUD / NUMBER
- WALL TYPE CALLOUT
- DOOR DESIGNATION CALLOUT
- WINDOW DESIGNATION CALLOUT
- ROOM / SPACE TAG
- DIMENSION LINE
- CENTER LINE
- PROPERTY LINE
- RATED SHAFT ENCLOSURE
- EXIT LIGHT
- FIRE EXTINGUISHER CABINET
- CORNER GUARD

SHEET NOTES

1. GENERAL REQUIREMENTS: SPECIFIED IN SECTION 01 10 00.

SUITE AREA SUMMARY

TYPE	SF	Level	Level	Level	TOTAL
1BR	772	7	8	8	23
ST	531	9	7	7	23
BUILDING SERVICE					1
CORE	399				3
SPINE	975				5
TENANT SUITE	672				9
TOTAL					64

STATEMENT OF SPECIAL INSPECTIONS

SECTION (SYSTEM): ITEM -- FREQUENCY -- STATUS

TABLE 1705.3 ITEM 1 (CAST IN PLACE CONCRETE): REINFORCEMENT AND PRESTRESSING TENDON PLACEMENT -- PERIODIC -- REQUIRED
TABLE 1705.3 ITEM 2 (CAST IN PLACE CONCRETE): REINFORCING BAR WELDING -- PERIODIC -- NOT PROVIDED — BY OTHERS
TABLE 1705.3 ITEM 3 (CAST IN PLACE CONCRETE): ANCHORS CAST IN CONCRETE -- PERIODIC -- REQUIRED
TABLE 1705.3 ITEM 4 (CAST IN PLACE CONCRETE): ANCHORS POST-INSTALLED IN HARDENED CONCRETE -- PERIODIC -- NOT PROVIDED — BY OTHERS
TABLE 1705.3 ITEM 5 (CAST IN PLACE CONCRETE): REQUIRED DESIGN MIX -- PERIODIC -- REQUIRED
TABLE 1705.3 ITEM 6 (CAST IN PLACE CONCRETE): STRENGTH SPECIMENS, SLUMP, AIR AND TEMPERATURE -- CONTINUOUS -- REQUIRED
TABLE 1705.3 ITEM 7 (CAST IN PLACE CONCRETE): CONCRETE PLACEMENT -- CONTINUOUS -- REQUIRED
TABLE 1705.3 ITEM 8 (CAST IN PLACE CONCRETE): CURING TEMPERATURE AND TECHNIQUES -- PERIODIC -- REQUIRED
TABLE 1705.3 ITEM 13 (CAST IN PLACE CONCRETE): IN-SITU STRENGTH BEFORE STRESSING AND BEFORE REMOVING SHORES AND FORMS -- PERIODIC -- REQUIRED
TABLE 1705.3 ITEM 14 (CAST IN PLACE CONCRETE): FORMWORK SHAPE, LOCATION AND DIMENSIONS -- PERIODIC -- REQUIRED
TABLE 1705.3 ITEM 9A (POST TENSIONED CONCRETE): APPLICATION OF PRESTRESSING FORCES -- CONTINUOUS -- REQUIRED
TABLE 1705.3 ITEM 9B (POST TENSIONED CONCRETE): GROUTING OF BONDED PRESTRESSING TENDONS -- CONTINUOUS -- NOT PROVIDED — BY OTHERS
TABLE 1705.6 ITEM 1 (SHALLOW FOUNDATIONS): MATERIALS BELOW SHALLOW FOUNDATIONS -- PERIODIC -- REQUIRED
TABLE 1705.6 ITEM 2 (SHALLOW FOUNDATIONS): EXCAVATION DEPTH AND MATERIAL -- PERIODIC -- REQUIRED
TABLE 1705.6 ITEM 3 (SHALLOW FOUNDATIONS): COMPACTED FILL CLASSIFICATION AND TESTING -- PERIODIC -- NOT PROVIDED — BY OTHERS
TABLE 1705.6 ITEM 4 (SHALLOW FOUNDATIONS): FILL PLACEMENT, DENSITIES AND LIFTS -- CONTINUOUS -- NOT PROVIDED — BY OTHERS
TABLE 1705.6 ITEM 5 (SHALLOW FOUNDATIONS): SUBGRADE BEFORE FILL -- PERIODIC -- NOT PROVIDED — BY OTHERS
1704.2.5 (PREFABRICATED FLOOR TRUSSES): FABRICATION OF FLOOR TRUSSES FT-1 -- DURING FABRICATION -- REQUIRED
1705.5.2 (PREFABRICATED FLOOR TRUSSES): TRUSS RESTRAINT AND BRACING, FT-1 -- PER SECTION -- NOT REQUIRED
1704.2.5 (PREFABRICATED FLOOR TRUSSES): FABRICATION OF FLOOR TRUSSES FT-2 -- DURING FABRICATION -- REQUIRED
1705.5.2 (PREFABRICATED FLOOR TRUSSES): TRUSS RESTRAINT AND BRACING, FT-2 -- PER SECTION -- NOT REQUIRED
1705.5.1 (WOOD LIGHT FRAME SFRS): HIGH-LOAD DIAPHRAGMS -- PER 1704.2 -- NOT REQUIRED
1705.13.2 (WOOD LIGHT FRAME SFRS): SEISMIC FASTENING OF WS-1 (8D @ 6/12) -- PERIODIC -- NOT REQUIRED
1705.13.2 (WOOD LIGHT FRAME SFRS): SEISMIC FASTENING OF WS-2 (8D @ 4/12) -- PERIODIC -- REQUIRED
1705.13.2 (WOOD LIGHT FRAME SFRS): SEISMIC FASTENING OF WS-3 (8D @ 3/12) -- PERIODIC -- REQUIRED
1705.12 (WOOD LIGHT FRAME SFRS): WIND-RESISTANCE FASTENING, ROOF AND WALL COVERING -- PERIODIC -- NOT PROVIDED — BY OTHERS
1705.13.6 (EMERGENCY STANDBY POWER): ANCHORAGE OF EMERGENCY AND STANDBY POWER EQUIPMENT -- PERIODIC -- NOT PROVIDED — BY OTHERS
1705.13.6 (AUTOMATIC SPRINKLER): EQUIPMENT CLEARANCES TO SPRINKLER DROPS AND SPRIGS -- PERIODIC -- REQUIRED
1705.13.6 (ELECTRICAL EQUIPMENT): ANCHORAGE OF OTHER ELECTRICAL EQUIPMENT -- PERIODIC -- NOT REQUIRED
1705.13.5 (NONSTRUCTURAL COMPONENTS): EXTERIOR CLADDING, NONBEARING WALLS AND VENEER -- PERIODIC -- NOT PROVIDED — BY OTHERS
1705.13.4 (NONSTRUCTURAL COMPONENTS): DESIGNATED SEISMIC SYSTEMS -- EXAMINE LABEL, ANCHORAGE AND MOUNTING -- NOT PROVIDED — BY OTHERS
1705.18 (FIRE RESISTANCE RATED ASSEMBLIES): THROUGH-PENETRATION FIRESTOPS AND FIRE-RESISTANT JOINTS -- PER SECTION -- REQUIRED

NOTES: SPECIAL INSPECTORS SHALL BE APPROVED BY THE AHJ PRIOR TO SPECIAL INSPECTION. S0.1 CARRIES THE SAME STATEMENT WITH THE DESIGN DATA.

NOT PROVIDED — BY OTHERS
APPLICANT / OWNER

CONSULTANTS

STRUCTURAL	NOT PROVIDED — BY OTHERS
CIVIL	NOT PROVIDED — BY OTHERS
MECHANICAL	NOT PROVIDED — BY OTHERS
PLUMBING	NOT PROVIDED — BY OTHERS
ELECTRICAL	NOT PROVIDED — BY OTHERS
LANDSCAPE	NOT PROVIDED — BY OTHERS
FIRE PROTECTION	NOT PROVIDED — BY OTHERS
GEOTECHNICAL	NOT PROVIDED — BY OTHERS

REVIEW

Prepared for review by the design professional of record. Not for construction or permit submission.

PROJECT

Architecture,Engineering — L courtyard study

FICTIONAL STUDY: NO REAL PARCEL
ARCHITECTURE,ENGINEERING — L COURTYARD STUDY
OCCUPANCY R-2, M · CONSTRUCTION NOT PROVIDED — BY OTHERS · STORIES 4

REVISIONS

MARK	DATE	DESCRIPTION

REGISTER

Project	AE-STUDY-L01
Issue	NOT PROVIDED — BY OTHERS
Date	NOT PROVIDED — BY OTHERS
Drawn	NOT PROVIDED — BY OTHERS
Scale	NTS
Phase	CONSTRUCTION DOCUMENTS

OPEN ISSUE

The set's open issue is stated on the cover, G0.01.

ABBREVIATIONS, SYMBOLS & GENERAL INFORMATION

SHEET

G0.07