PLUMBING FIXTURE SCHEDULE (COUNTS VS CITED MINIMUM)

FIXTURE	COUNT	BASIS	PRODUCT	STATUS
DISHWASHER	23	SEE PLB-002	GE GDT535PSRSS	VERIFY
KITCHEN SINK	47	46/UNIT	KOHLER VERSE K-5267-3	VERIFY
LAVATORY	47	46/UNIT	KOHLER VEER K-5248-1	VERIFY
SHOWER	47	46/UNIT	KOHLER RITE-TEMP K-304-K	VERIFY
WATER CLOSET	47	46/UNIT	KOHLER WELLWORTH K-3998	VERIFY

WATER DEMAND (WSFU / HUNTER)

QUANTITY	VALUE	METHOD
TOTAL WSFU	300.1	IPC T E103.3(2)
PEAK DEMAND	105 GPM	IPC T E103.3(3)
TOTAL DFU	422.0	IPC T709.1
BOOSTER PUMP	NOT PROVIDED — BY OTHERS	PRESSURE BUDGET

PLUMBING EQUIPMENT

SYSTEM	COUNT	SIZE/CAPACITY	MATERIAL	STATUS
WASTE STACKS	NOT PROVIDED — BY OTHERS	SEE RISER	CAST IRON / PVC	—
SPRINKLER HEADS	NOT PROVIDED — BY OTHERS	—	UL-LISTED WET PIPE	DATA AT DD

SHEET NOTES

1. PLUMBING: SPECIFIED IN SECTION 22 11 00.

NOT PROVIDED — BY OTHERS
APPLICANT / OWNER

CONSULTANTS

STRUCTURAL	NOT PROVIDED — BY OTHERS
CIVIL	NOT PROVIDED — BY OTHERS
MECHANICAL	NOT PROVIDED — BY OTHERS
PLUMBING	NOT PROVIDED — BY OTHERS
ELECTRICAL	NOT PROVIDED — BY OTHERS
LANDSCAPE	NOT PROVIDED — BY OTHERS
FIRE PROTECTION	NOT PROVIDED — BY OTHERS
GEOTECHNICAL	NOT PROVIDED — BY OTHERS

REVIEW

Prepared for review by the design professional of record. Not for construction or permit submission.

PROJECT

Architecture.Engineering — L courtyard study

FICTIONAL STUDY: NO REAL PARCEL
ARCHITECTUREENGINEERING — L COURTYARD STUDY
OCCUPANCY R-2, M · CONSTRUCTION NOT PROVIDED — BY OTHERS · STORIES 4

REVISIONS

MARK	DATE	DESCRIPTION

REGISTER

Project	AE-STUDY-L01
Issue	NOT PROVIDED — BY OTHERS
Date	NOT PROVIDED — BY OTHERS
Drawn	NOT PROVIDED — BY OTHERS
Scale	NTS
Phase	CONSTRUCTION DOCUMENTS

OPEN ISSUE

The set's open issue is stated on the cover, G0.01.

PLUMBING FIXTURE & EQUIPMENT SCHEDULE

SHEET

P3.1